

Technical Data Sheet (TDS)

XTR14 Trowel #14

Special features

- for installation of Engineered Floors
- when both the Flooring and the Sub Floor are flat



Trowel Notches



Packaging Size

- 10 count Case

For Installation of

- Engineered Wood Flooring

Spread Rate

- Engineered Floors-#14 (3/16"x1/4"x9/16") up to 85SF/gal (sub floor/flooring gap 1/8" max)

Depth of each Tooth

- 3/16"

Width of each Tooth

- 1/4"

Space between Teeth

- 9/16"